

बिहार राज्य पुल निर्माण निगम लिमिटेड



(बिहार सरकार का एक प्रतिष्ठान)
वरीय परियोजना अभियंता का कार्यालय
कार्य प्रमंडल, गया।

वेबसाईट <http://brpnnl.bihar.gov.in> ई-मेल e-mail : spe-gaya@brpnn.co.in

Doc. No:-BRPNNL/GAY/C003/ 428

Dt.: 06/06/2026

Short Notice Inviting Quotation

Sealed Quotations are invited from B.R.P.N.N.Ltd., Empanelled Works Contractors/ Agencies for Repair & retrofitting work of damaged H.L. R.C.C. Bridge Over Muhane River Between Bataspur & Silaunja Village in District of Gaya.

Rates should be inclusive materials, labour & Carraige cost with all relevant taxes including GST.

Sl. No.	Name of work	Estimate Amount (Rs. In Lacs)	EMD Amount (in Rs.)	Cost of B.O.Q Amount (in Rs.)	Work Period	Remarks
1.	Repair & retrofitting work of damaged H.L. R.C.C. Bridge Over Muhane River Between Bataspur & Silaunja Village in District of Gaya.	Rs. 93.58	Rs. 1,87,154/-	Rs 5,000/-	06 (Six) Month	BOQ Attached

Sl. No.	Activity	Duration
1.	Download date of bid documents	From – 10.06.2026 (10:00 Hrs.) to 17.06.2026.(15:00 Hrs.) (www.brpnnl.bihar.gov.in)
2.	Last Date/Time for submission of offer/Bid	17.06.2026 upto 15:00 Hrs. (www.brpnnl.bihar.gov.in)
3.	Date & time for opening of offer/Bid	17.06.2026 upto 16:00 Hrs. (www.brpnnl.bihar.gov.in)


The sealed quotation will be received in the office of the undersigned upto 03:00 p.m on or before date 17.06.2026 and will be opened on 17.06.2026 on 04:00 p.m. Interested Empanelled works contractors/agencies may download the BOQ from our website: www.brpnnl.bihar.gov.in. The Empanelled works contractors/ agencies or their authorized representative may be present at the time of opening of the quotations. The envelopes should be addressed to "Senior Project Engineer, Work Division, Gaya, Bihar Rajya Pul Nirman Nigam Ltd.," mentioning the name and scope of the work on the envelop. If an envelope is received through post or by hand and is found opened inadvertently, BRPNNL will not be responsible and the quotation may not be considered even if quoting lowest rates. The quotationer should submit PAN, GST & empanelment letter of B.R.P.N.N.Ltd., Work Circle-1 along with rate proposal. The B.R.P.N.N.Ltd. reserves the right to accept or reject any or all proposals without resigning any reason thereof.

06/06/2026
Senior Project Engineer
B.R.P.N.N.Ltd
Works Division, Gaya

06/06/2026

Terms and Conditions :-

- i. Cost of Earnest Money & B.O.Q Amount is mandatory.
- ii. The firm should have empanelment as Contractor in BRPNNL.
- iii. Rate quoted shall be inclusive of all type of Taxes, Cess etc.
- iv. Cost of Earnest Money Rs 1,87,154.00 (Rs One Lakh Eighty Seven Thousand One Hundred Fifty Four) only to be paid only offline mode i.e Fixed Deposit/D.D shall be fully endorsed/pledged to the Senior Project Engineer, BRPNNL, Works Division, Gaya should be valid not for less than 165 days from last date of submitting of tender document.
- v. Cost of B.O.Q amount Rs 5,000.00 (Five Thousand) only to be paid only offline mode i.e Demand Draft in favour of Senior Project Engineer, BRPNNL, Works Division, Gaya, Payable at Gaya from last date of submitting of tender document.
- vi. All the submitted documents shall have the signature of bidder or their authorized signatories.
- vii. The envelopes should be addressed to "Senior Project Engineer, Work Division, Gaya, Bihar Rajya Pul Nirman Nigam Ltd.," mentioning the name and scope of the work on the envelop.
- viii. The bidder also must enclose affidavit for Debar / Blacklist.
- ix. Defect Liability Period - 01 (One) Year.
- x. Under signatory reserves the right to accept or reject any or all proposals and cancel quotation without assigning any reason thereof.


06/06/2026
Senior Project Engineer
B.R.P.N.N.Ltd
Works Division, Gaya


06/06/2026


06.06.26

Bill of Quantity for Repair & retrofitting work of damaged H.L. R.C.C. Bridge Over Muhane River Between Bataspur & Silaunja Village in District of Gaya.

Sl. No.	SOR	Description	Unit	Quantity	Rate	Amount
1	RCD SOR 12.01	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material.	Cum	456.994		
2	TEC RWD	Laying Brick soling layer on prepared sub-grade with brick on lines, graded and cross-section shown on the drawing filling joints with sand and earth as per Technical Specification Clause 412	Sqm	214.792		
3	RCD SOR 17.09	Removal of defective concrete, cleaning the surface thoroughly, applying the shotcrete mixture mechanically with compressed air under pressure, comprising of cement, sand, coarse aggregates, water and quick setting compound in the proportion as per clause 2807.1 sand and coarse aggregates conforming to IS:383 and table 1 of IS: 9012 respectively, water cement ratio ranging from 0.35 to 0.50, density of gunite not less than 2000 kg/cum, strength not less than 25 Mpa and workmanship conforming to clause 2807.6.	Sqm	219.857		
4		Cleaning of rebars : Removal of all rust materials, cleaning of corroded reinforcement by wire brush, then clean with air blower/water jet and finally cleaning by rust-remover, cleaning & etching agent Reebaklens RR a combination of acid based material, corrosion inhibitors and dispersing agents and is supplied as a clear green solution.-having no corrosive action and which easily penetrates grease and oil.	Sqm	65.957		
5	ASSAM PWD SOR(18-19) Item No.16.26 A	Anti-corrosion coating of rebars: Supplying and applying two coats of Zinc rich anti-corrosive protective coating with 'Techguard102' of Choksey Chemicals or equivalent @ 0.50 Lit per Sqm over thoroughly cleaned and prepared steel bars including formwork as directed and specified by the department complete.	SqM	65.957		
6	RCD Bihar 17.04	Providing and inserting nipples with approved fixing compound after drilling holes for grouting as per technical Specifications including subsequent cutting/removal and sealing of the hole as necessary of nipples after completion of grouting with Cement/Epoxy	Nos.	528		
7	RCD Bihar 17.07	Sealing of crack/porous concrete with Epoxy Grout by injection through nipples complete as per clause 2803.1	Kg	132.00		
8	RCD Bihar 17.08	Applying epoxy mortar over leached, honey combed and spalled concrete surface and exposed steel reinforcement complete as per Technical Specification.	Sqm	53.24		
9	RCD Bihar 17.10	Applying pre-packed cement based polymer mortar of strength 45 Mpa at 28 days for replacement of spalled concrete	Sqm	0.00		
10	ASSAM PWD SOR(18-19) Item No.16.31	Application of Micro Concrete for concrete jacketing : Concreting of the structure with free flow nonshrink cementitious microconcrete with Rendorec RG of Fosroc or equivalent after proper mixing with cleanwater including formwork followed by proper curing for 28 days as per manufacturer's specifications complete and as directed by the Department	CuM	95.333		
TOTAL AMOUNT (INCLUDING OF ALL TAXES)						

26/06/2026

[Signature]

26/06/2026